2.5 - INSPECTION PROCEDURE SUMMARY (Continued)

This form KA-008 is kept as part of the work order record.

Each technician and inspector have a unique login name/password and a unique code to enter into the "sign-off categories" section of EBIS. The code will represent the name of the person who performed the work and is usable by only the respective employee.

Upon completion of each individual task of the in progress inspection, the area is given an inspection. If the inspector finds discrepancies, he informs the technician doing the work and either enters the discrepancy into EBIS or records on form KA-008. After all rework of the discrepancies found by the inspector is accomplished, the technician notifies the inspector, and the work is submitted for final inspection and acceptance.

Upon completion of a specific operation, the technician will enter the corrective action under the work order discrepancy and once completed will change the Item status block in EBIS, for that discrepancy to "Insp. Required" indicating that the item is complete and ready for inspection. The inspector will then inspect the item to assure conformance to specifications. The Operational, Functional or Leak test (as applicable) of any system affected by the work involved will be accomplished and signed off by the Employee with their code. An inspector's code will be used to sign off the applicable in process inspection, Panel OK to close and final inspection on each discrepancy.

- Definitions
  - In Process Inspection- Sign-off by Inspector inspecting the task in process.
  - Functional Check- Sign-off by Employee performing the Functional Check as per the task Maintenance Manual
  - Operational Check- Sign-off by Employee performing the Operational Check as per the task Maintenance Manual
  - Leak Check- Sign-off by Employee performing the Leak Check as per the task Maintenance Manual
  - Panel OK to Close- Sign-off by Inspector approving the panels to be closed
  - Final Inspection- Sign-off by Inspector upon satisfactory completion of task to include discrepancy corrective action entered

NOTE: At times, due to availability of personnel, and location an inspector may need to perform the work and then on completion, inspect his/her own work. This will be authorized verbally by the Accountable Manager and will be subject to the guidelines set forth for each specific instance. All required tests and inspections must be performed. This is best accomplished by performing the work completely including paperwork as the technician. Then going back and inspecting all of the work including paperwork as an inspector. In other words split the job as if two people were actually doing the work.

2.6 PRELIMINARY INSPECTION

A Preliminary Inspection will be performed by a qualified inspector assigned by the Accountable Manager on each article authorized under the repair station's FAA approved ratings prior to beginning work on the article. The Preliminary Inspection will be signed off in EBIS by the inspector upon completion and all of the discrepancy findings will be documented in EBIS or on the Discrepancy Evaluation Technician Notes form KA-008. Inspector will disposition per KA-008 instructions. Discrepancy findings entered into EBIS will be assured corrective action is completed, inspected, and accepted prior to release for return to service. The work will be reinspected until found satisfactory, or the article will be rejected for return to service approval. In the event that EBIS is not available, it will be documented on the paper work order form KA-005.