MAYO
AVIATION

Proposal

ADS-B Mandate Upgrade

Installation of Garmin G600 TXi, GTN-650 Touchscreen GPS/NAV/COM
and GTX-345R/335R Transponders for ADS-B In & Out

Banner Health
Piper Cheyenne N75TW, S/N: 8004016

MAYOAVIATION.COM

January 6, 2017

Scott Bell
Banner Health
1801 16th Street
Greeley, Colorado 80631
970-381-6097

Aircraft Make:	Piper
Aircraft Model:	Cheyenne I
Aircraft Serial:	31T-8004016
Registration No.:	N75TW
Quote No.:	2018-01-06

Dear Mr. Scott Bell,

Thank you for considering Mayo Aviation for your aircraft service needs. We are pleased to present you with this proposal for the work specified on your aircraft. A summary of the requested work is below. Detailed information follows.

Item Description	Quoted Price
Installation of Garmin's G600 TXi Primary Flight Display a Garmin GTN-650 NAV/COM/WAAS GPS a Garmin GNC-255A Nav/Com a GMA-342 Audio Panel, GTX-345 and GTX-335 Transponders for ADS-B In and Out and a L3 ESI-500 Standby Instrument indicator with Nav two display.	$88,500.00
Installation of a Stratus Cabin USB Charging Ports	$900.00 each

At Mayo Aviation, we strive to provide our customers with unequaled customer service and quality workmanship. All work performed by our technicians on your aircraft will meet or exceed the quality and safety standards established by the Federal Aviation Administration.

I appreciate that you are giving Mayo Aviation the opportunity to provide you with this proposal. I look forward to working with you in the near future. If you have any questions or concerns, please contact me at your convenience.

Warm Regards,

James Bohart

James Bohart
Avionics Manager
Mayo Aviation, Inc.
Mobile: 864-804-8411
Email: jamesb@mayoaviation.com

PROPOSAL DETAILS

1. **Installation of Garmin G600 TXi Primary Flight Display, GTN-650 NAV/COM/WAAS GPS system, GNC-255A Nav/Com, GMA-342 Audio Panel, GTX-345 and GTX-335 Transponders for ADS-B In and Out and a L3 ESI-500 Standby indicator.**

   The installation will include the following:

   - Remove Existing radio package, racks and all unused wiring and connectors
   - Install a new Garmin 10" G600 TXi Primary Flight Display
     - 10" GDU-1060 Display with internal AHRS
     - GMU-44 Magnetometer
     - GDU-700/1060 Digital Air Data Computer
     - GAD-43E digital ARINC adapter for autopilot functions
     - GTP-59 Temperature Probe
     - G600 Americas Database Card
   - Install a new Garmin GTN-650 NAV/COM/WAAS GPS
     - GTN-650 Unit
     - GA-35 WAAS/GPS Antenna
     - GTN Americas Database Card
   - Install a Garmin GNC-255A Nav/Com
     - Existing Nav and Com antennas will be retained
   - Install a Garmin GMA-342 Audio Panel
   - Install a new Garmin GTX-345R ADS-B In and Out Transponders
     - Existing Transponder antenna will be retained
   - Install a new Garmin GTX-335R ADS-B Out Transponders
     - Existing Transponder antenna will be retained
   - Install a new L3 ESI-500Electronic Standby Instrument System

- Display the number two GNC-255A navigation information

- ✈ Refurbish Existing Instrument Panel to accommodate the new fight and navigation equipment
- ✈ Installation Materials
- ✈ Installation Labor
- ✈ Engineering Charges
- ✈ Garmin STC Certification

Total Engineering, Labor and Materials. . . . . $88,500.00 Accept ☐ Declined ☐

NOTE: The existing GPS, NAV's, COM's, Transponders, ADF, RMI, audio system, Pilots flight displays and existing wiring and associated components (retaining all antennas except the GPS) will be removed. A new Garmin system will be installed consisting of pilot's primary flight display, WAAS GPS/NAV/COM System (#1 system), NAV/COM (#2 system), dual ADS-B Transponders for ADS-B In and OUT, a new digital Audio Panel and an Electronic Standby Instrument on the pilot's panel.

The existing systems that are retained will be evaluated for proper operation and compatibility with the new equipment, this includes the existing traffic system. The Existing Radar, Multi-Function Display (MFD) will be retained.

The pilots instrument panel and center radio panel will be remanufactured to best fit the new equipment and retained existing equipment.

2. Optional: Installation of Stratus Cabin USB Charging ports.

The installation will include the following:

- ✈ Install a new Stratus USB Charging port.
- ✈ Installation Materials
- ✈ Installation Labor

Enjoy the convenience of USB power in your aircraft — delivered by the durable, high-quality engineering and with enough power to charge two full-size iPads while they're in use, the Stratus Power USB charging port can be used with any combination of portable electronic devices.

Note: Charging ports are normally installed near the card table on the right side of the aircraft, more than one can be installed giving easy access to the charging port on both sides of the aircraft.

Total Engineering, Labor and Materials. . . . . . **$900.00 each** Accept ☐ Declined ☐

Note: This proposal is provided without a complete equipment survey of the aircraft, every aircraft configuration is different, and this proposal is given with every effort to be complete and accurate. It is possible that there may be needed changes once the aircraft is inducted and a complete and through inspection and testing of the systems.

Note: The original Avionics and any modification wiring diagrams are required to complete the proposed upgrade. If the original aircrafts Avionics wiring diagrams are not available replacements will be ordered if available and will be an additional expense to the customer.

PROJECT INFORMATION

DOWN-TIME

Estimated downtime is 20 -25 working days. All downtime estimates assume adequate lead-time is provided. Downtime is dependent upon the customer's compliance with the lead-time requirements specified above and delivery of the aircraft/components by the agreed upon time on the induction date.

Aircraft/component logbooks must accompany aircraft at time of induction. Additional down time may be required for changes to the scope of work, or other unforeseen circumstances and is not guaranteed or warranted in any

form. Mayo Aviation is not responsible for delays incurred as a result of forces beyond our reasonable control, including, but not limited to vendor delays, failure of transportation, delays in the attainment of FAA approvals, etc.

LEAD-TIME

Adequate lead-time is a critical component to the ability to meet the estimated delivery time, as vendor delivery requirements are outside Mayo Aviation's control and must be provided for. Lead-time required for this project is subject to our confirmation of space, time required for equipment procurement and manpower availability.

PRICING

Pricing is as described in the work scope. Prices stated herein are based on U.S. dollars and are exclusive of Federal, State and local taxes, airport fees and applicable freight charges and are valid for a period of thirty (30) days. Parts prices included in this proposal are subject to change without notice. Mayo Aviation reserves the right to pass pricing increases through to the customers, which are necessitated by state or federal governmental regulatory changes, if applicable. All removed equipment becomes the property of Mayo Aviation.

The quoted prices do not include clearing discrepancies, Service Bulletins, or Airworthiness directives. Discrepancies will be reviewed with the customer's authorized representative for approval prior to corrective action. Any discrepancies, Service Bulletins, or Airworthiness Directives requiring action will be handled on a time and materials basis at the prevailing shop rates.

PERFORMANCE OF WORK SCOPE

A Maintenance and/or Repair Authorization form will be provided upon acceptance of this quote for your convenience. The work scope will be added, and room will be reserved for any discrepancies requiring attention. Mayo Aviation must receive the signed authorization form no later than aircraft induction.

All estimates are based on completion in accordance with FAA standards. In the event the company standards exceed those required by the FAA, Mayo Aviation reserves the right to adjust the pricing provided in this document. Should the Customer request additions, and/or changes to the Work scope, they will be handled on a time and materials basis.

ADDITIONAL INFORMATION

The FAA has varying interpretations of Continuing Airworthiness requirements. This proposal was prepared based on our understanding of the current requirements. However, in the event Continuing Airworthiness documentation is required as a result of a different interpretation, it will be considered additional and addressed on a time and material basis. Appropriate engineering and DER charges could apply.

This quote assumes that space is available for the new installations and other equipment unless otherwise specifically stated in the work scope. It also assumes adequate electrical interfaces and power exist in the aircraft for the proposed installation and that the work scope can be accomplished without any structural modifications. Should relocation or other modification be required, it will be considered additional and addressed on a time and material basis and appropriate DER charges will apply.

TERMS AND CONDITIONS

The work scope covered by this quotation is subject to Mayo Aviation's standard terms and conditions. Please see Mayo Aviation's work authorization document for the applicable terms and Conditions.

PAYMENT TERMS

Mayo Aviation agrees to accept two payments for the above work scope. The first payment will be equal to 50% of the proposal amount and will be due at the time of proposal acceptance. The final payment will be equal to the account balance and is due upon aircraft delivery.

Overhaul exchange pricing assumes the return of your units to the appropriate overhaul facility, which Mayo Aviation will take care of. Charges assessed by these vendors to bring cores up to their exchange criteria will be invoiced additionally as applicable.

Any warranties provided by Mayo are contingent upon payment in full according to Mayo Aviation' established credit terms for services rendered.

CUSTOMER ACCEPTANCE

The customer hereby agrees to the proposal presented herein and authorizes the above work scope. The customer represents that he or she is employed by the customer in the capacity indicated and is unequivocally authorized to bind the customer to this agreement.

Mayo Aviation hereby agrees to perform the work specified in this agreement. The parties agree that at the time of the execution hereof, there are no agreements, understandings, conditions, warranties, guarantees or, representations, oral or written, express or implied, with respect to the subject matter of Mayo Aviation's terms and conditions that are not hereby merged or superseded.

_____ _____

Accepted Date

For: Banner Health