MAYO
AVIATION

Proposal

Installation of Garmin G600 Primary Flight Display and Dual GTX-335(R) Transponders for ADS-B Out

Dawna Mauldin
Beechcraft King Air B200 S/N BB-887

November 16, 2017

Dawna Mauldin
PO BOX 1794
Pampa, Texas 79066

Aircraft Make:	Beechcraft
Aircraft Model:	B200
Aircraft Serial:	BB-887
Registration No.:	N87699
Quote No.:	2017-11-16

Dear Dawna,

Thank you for considering Mayo Aviation for your aircraft service needs. We are pleased to present you with this proposal for the work specified on your aircraft. A summary of the requested work is below. Detailed information follows.

Item Description	Quoted Price
Installation of Garmin 10” G600 TXi (GDU-1060) Primary Flight Display, New GTN-650 Nav/Com/WAAS GPS, GNS-255A Nav/Com and Dual GTX-335 (R) Transponders for ADS-B Out	$81,400.00
Installation of Garmin 7” G600 TXi (GDU-700P) Primary Flight Display, New GTN-650 Nav/Com/WAAS GPS, GNS-255A Nav/Com and Dual GTX-335 (R) Transponders for ADS-B Out	$76,500.00
Installation of a Garmin Flightstream 510 wireless transmitter Data Card	$1,350.00
Installation of a Stratus Cabin USB Charging Ports	$950.00 Each

At Mayo Aviation, we strive to provide our customers with unequaled customer service and quality workmanship. All work performed by our technicians on your aircraft will meet or exceed the quality and safety standards established by the Federal Aviation Administration.

I appreciate that you are giving Mayo Aviation the opportunity to provide you with this proposal. I look forward to working with you here in the near future. If you have any questions or concerns, please contact me at your convenience.

Warm Regards,

James Bohart

James Bohart
Avionics Manager
Mayo Aviation, Inc.
Mobile: 864-804-8411
Email: jamesb@mayoaviation.com

PROPOSAL DETAILS

1. **Installation of Garmin 10" G600 TXi Primary Flight Display, a new GTN-650 NAV/COM/ WAAS GPS and two GTX-335 (R) Transponders for ADS-B Out**

   The installation will include the following:

   - Remove the pilots flight instruments including the existing NAVS, COMS, ADF, DME pilots and copilots RMI's and Bendix King KLN-94 GPS.
   - Remove the existing transponders.
   - Remove the existing Audio System
   - Install new Garmin G600 TXi Primary Flight display with internal AHRS
   - Install a new Garmin Digital ADC-74
   - Install a new Garmin GMU-44 Magnetometer.
   - Install a new Garmin GTN-650 NAV/COM/WAAS GPS with SD Database, Install Kit and Pilot Guide.
   - Install a new Garmin GMA-342 Audio Panel
   - Install new Garmin GA 35 GPS/WAAS antenna
   - Install two new Garmin GTX-335 (R) Transponder
   - Install a new L3 ESI-500 Standby Instrument / #2 CDI on the pilot's instrument panel
   - Relocate the Removed pilots HSI and ADI Instruments to the copilot's panel for display of existing Heading and Attitude information.
   - Install a new Garmin GNC-255A NAV/COM as the number two system.
   - Re-manufacture the instrument panel for the new avionics.
   - Retain the existing Bendix King MFD, TAWS and Radar.
   - Installation Materials
   - Installation Labor
   - Engineering Charges
   - Garmin Beechcraft King Air B200 STC Certification

   The installation will consist of removing the existing pilots Flight instruments and relocating the ADI and HSI to the copilot's panel remove existing GPS, both transponders systems, DME, ADF and both

pilots and copilots RMI's and install a Garmin **10 inch** G600 NXI System in the pilot's panel, a Garmin GTN-650 NAV/COM/WAAS GPS interfaced to the autopilot and the G600 NXi, two new GTX-335 (R) transponders for ADS-B Out.

The existing Bendix King MFD, Radar and TAWS systems will be retained.

The center radio panel will be remanufactured and refurbished to accommodate the new equipment and will retain some of the existing switches and components where needed.

Total Engineering, Labor and Materials. . . . . $81,400.00 Accept ☐ Declined ☐

2. Installation of Garmin 7" G600 TXi Primary Flight Display, a new GTN-650 NAV/COM/ WAAS GPS and two GTX-335 (R) Transponders for ADS-B Out

The installation will include the following:

- Remove the pilots flight instruments including the existing NAVS, COMS, ADF, DME pilots and copilots RMI's and Bendix King KLN-94 GPS.
- Remove the existing transponders.
- Remove the existing Audio System
- Install new Garmin G600 TXi Primary Flight display with internal AHRS
- Install a new Garmin Digital ADC-74
- Install a new Garmin GMU-44 Magnetometer.
- Install a new Garmin GTN-650 NAV/COM/WAAS GPS with SD Database, Install Kit and Pilot Guide.
- Install a new Garmin GMA-342 Audio Panel
- Install new Garmin GA 35 GPS/WAAS antenna
- Install two new Garmin GTX-335 (R) Transponder
- Install a new L3 ESI-500 Standby Instrument / #2 CDI on the pilot's instrument panel

- Relocate the Removed pilots HSI and ADI Instruments to the copilot's panel for display of existing Heading and Attitude information.
- Install a new Garmin GNC-255A NAV/COM as the number two system.
- Re-manufacture the instrument panel for the new avionics.
- Retain the existing Bendix King MFD, TAWS and Radar.
- Installation Materials
- Installation Labor
- Engineering Charges
- Garmin Beechcraft King Air B200 STC Certification

The installation will consist of removing the existing pilots Flight instruments and relocating the ADI and HSI to the copilot's panel remove existing GPS, both transponders systems, DME, ADF and both pilots and copilots RMI's and install a Garmin **7 inch** G600 NXI System in the pilot's panel, a Garmin GTN-650 NAV/COM/WAAS GPS interfaced to the autopilot and the G600NXi, two new GTX-335 (R) transponders for ADS-B Out.

The existing Bendix King MFD, Radar and TAWS systems will be retained.

The center radio panel will be remanufactured and refurbished to accommodate the new equipment and will retain some of the existing switches and components where needed.

Total Engineering, Labor and Materials. . . . . $76,500.00 Accept ☐ Declined ☐

3. **Optional: Installation of a Garmin Flight Stream 510 Wireless transmitter.**

The installation will include the following:

- Install a new Garmin Flightstream 510 Data Card.
- Installation Labor

Flight Stream 510 is a small Wi-Fi and Bluetooth - enabled Multi-Media-Card (MMC) that enables communication between the GTN 650 and two compatible Apple® or Android™ mobile devices operating Garmin Pilot. Wi-Fi connectivity is specifically for Database Concierge wireless database transfer, and Bluetooth allows for a wide variety of additional capabilities, including flight plan transfer.

Total Engineering, Labor and Materials. . . . . $1.350.00 Accept ☐ Declined ☐

4. Optional: Installation of Stratus Cabin USB Charging ports.

The installation will include the following:

- ✈ Install a new Stratus USB Charging port.
- ✈ Installation Materials
- ✈ Installation Labor

Enjoy the convenience of USB power in your aircraft — delivered by the durable, high-quality engineering and with enough power to charge two full-size iPads while they're in use, the Stratus Power USB charging port can be used with any combination of portable electronic devices.

Note: Charging ports are normally installed near the card table on the right side of the aircraft, more than one can be installed giving easy access to the charging port on both sides of the aircraft.

Total Engineering, Labor and Materials. . . . . . **$900.00 each** Accept ☐ Declined ☐

Note: This proposal is provided without a complete equipment survey of the aircraft, every aircraft configuration is different and this proposal is given with every effort to be complete and accurate. It is possible that there may be needed changes once the aircraft is inducted and a complete and through inspection and testing of the systems.

Note: The original Avionics and any modification wiring diagrams are required to complete the proposed upgrade. If the original aircrafts Avionics wiring diagrams are not available replacements from Beechcraft will be ordered and will be an additional expense to the customer estimated at $300.00.

PROJECT INFORMATION

DOWN-TIME

Estimated downtime is estimated at 21 to 28 days. All downtime estimates assume adequate lead-time is provided. Downtime is dependent upon the customer's compliance with the lead-time requirements specified above and delivery of the aircraft/components by the agreed upon time on the induction date.

Aircraft/component logbooks must accompany aircraft at time of induction. Additional down time may be required for changes to the scope of work, or other unforeseen circumstances and is not guaranteed or warranted in any form. Mayo Aviation is not responsible for delays incurred as a result of forces beyond our reasonable control, including, but not limited to vendor delays, failure of transportation, delays in the attainment of FAA approvals, etc.

LEAD-TIME

Adequate lead-time is a critical component to the ability to meet the estimated delivery time, as vendor delivery requirements are outside Mayo Aviation's control and must be provided for. Lead-time required for this project is subject to our confirmation of space, time required for equipment procurement and manpower availability.

PRICING

Pricing is as described in the work scope. Prices stated herein are based on U.S. dollars and are exclusive of Federal, State and local taxes, airport fees and applicable freight charges and are valid for a period of thirty (30) days. Parts prices included in this proposal are subject to change without notice. Mayo Aviation reserves the right to pass pricing increases through to the customers, which are necessitated by state or federal governmental regulatory changes, if applicable. All removed equipment becomes the property of Mayo Aviation.

The quoted prices do not include clearing discrepancies, Service Bulletins, or Airworthiness directives. Discrepancies will be reviewed with the customer's authorized representative for approval prior to corrective action. Any discrepancies, Service Bulletins, or Airworthiness Directives requiring action will be handled on a time and materials basis at the prevailing shop rates.

PERFORMANCE OF WORK SCOPE

A Maintenance and/or Repair Authorization form will be provided upon acceptance of this quote for your convenience. The work scope will be added, and room will be reserved for any discrepancies requiring attention. Mayo Aviation must receive the signed authorization form no later than aircraft induction.

All estimates are based on completion in accordance with FAA standards. In the event the company standards exceed those required by the FAA, Mayo Aviation reserves the right to adjust the pricing provided in this document. Should the Customer request additions, and/or changes to the Work scope, they will be handled on a time and materials basis.

ADDITIONAL INFORMATION

The FAA has varying interpretations of Continuing Airworthiness requirements. This proposal was prepared based on our understanding of the current requirements. However, in the event Continuing Airworthiness documentation is required as a result of a different interpretation, it will be considered additional and addressed on a time and material basis. Appropriate engineering and DER charges could apply.

This quote assumes that space is available for the new installations and other equipment unless otherwise specifically stated in the work scope. It also assumes adequate electrical interfaces and power exist in the aircraft for the proposed installation and that the work scope can be accomplished without any structural modifications. Should relocation or other modification be required, it will be considered additional and addressed on a time and material basis and appropriate DER charges will apply.

TERMS AND CONDITIONS

The work scope covered by this quotation is subject to Mayo Aviation's standard terms and conditions. Please see Mayo Aviation's work authorization document for the applicable terms and Conditions.

PAYMENT TERMS

Mayo Aviation agrees to accept two payments for the above work scope. The first payment will be equal to 50% of the proposal amount and will be due at the time of proposal acceptance. The final payment will be equal to the account balance and is due upon aircraft delivery.

Overhaul exchange pricing assumes the return of your units to the appropriate overhaul facility, which Mayo Aviation will take care of. Charges assessed by these vendors to bring cores up to their exchange criteria will be invoiced additionally as applicable.

Any warranties provided by Mayo are contingent upon payment in full according to Mayo Aviation' established credit terms for services rendered.

CUSTOMER ACCEPTANCE

The customer hereby agrees to the proposal presented herein and authorizes the above work scope. The customer represents that he or she is employed by the customer in the capacity indicated and is unequivocally authorized to bind the customer to this agreement.

Mayo Aviation hereby agrees to perform the work specified in this agreement. The parties agree that at the time of the execution hereof, there are no agreements, understandings, conditions, warranties, guarantees or, representations, oral or written, express or implied, with respect to the subject matter of Mayo Aviation's terms and conditions that are not hereby merged or superseded.

_____ _____

Accepted Date

Dawna Mauldin

Beechcraft B200, N87699